

SCOPE OF WORKS — RETAIL FIT-OUT

Dubai Mall Annex — Unit R-047 | Ground Floor | Retail Fit-Out

Location: Dubai, UAE | Area: 320 m² | Currency: AED | Grade: Premium Retail

1. PROJECT OVERVIEW

This document defines the scope of works for the complete fit-out of retail unit R-047 at Dubai Mall Annex. The unit is a shell & core handover space. The fit-out includes all interior architectural works, MEP modifications, shopfront, and visual merchandising fixtures. All works must comply with Dubai Mall Tenant Fit-Out Guidelines (2024 edition) and Dubai Municipality regulations.

2. AREAS & DIMENSIONS

Zone	Area (m²)	Flooring	Ceiling Height
Sales Floor — Main	210	Polished Porcelain 800x800	4.5m
Sales Floor — Feature	45	Engineered Hardwood	4.5m (void above)
Fitting Rooms (6 No.)	30	LVT Vinyl Premium	2.8m
Stock Room	25	Epoxy Coating	4.5m (no suspended ceiling)
Staff Room & Toilet	10	Ceramic 400x400	2.8m
TOTAL	320	—	—

3. SCOPE ITEMS

Ref	Description	Unit	Qty	Rate (AED)	Total (AED)
A.01	Shopfront — frameless glass & aluminium (per mall guidelines)	lm	12	8,500	102,000
A.02	Internal glass partitions (fitting rooms)	m2	45	650	29,250
A.03	Polished porcelain tiles 800x800 (sales floor)	m2	210	195	40,950
A.04	Engineered hardwood flooring (feature area)	m2	45	380	17,100
A.05	Suspended ceiling — perforated metal (sales floor)	m2	255	420	107,100
A.06	Feature ceiling — backlit coffer (entrance)	m2	35	850	29,750
A.07	High-end emulsion paint (all walls, 3 coats)	m2	680	35	23,800
A.08	Feature wall — decorative cladding panels	m2	80	480	38,400
B.01	HVAC modifications (DEWA/Empower compliant)	ls	1	85,000	85,000
B.02	Electrical works (DB, lighting, power outlets)	ls	1	62,000	62,000
B.03	LED track lighting system (sales floor)	nr	85	420	35,700
B.04	Fire alarm & sprinkler modifications	ls	1	24,000	24,000
B.05	ELV systems (CCTV, access control, POS cabling)	ls	1	18,000	18,000
C.01	Built-in display shelving (bespoke, lacquered MDF)	lm	35	1,200	42,000
C.02	Cash wrap / cashier counter (custom)	nr	1	22,000	22,000
C.03	Fitting room furniture & mirrors	nr	6	3,500	21,000
	SUBTOTAL				697,050

	Contingency 10%				69,705
	Profit & Overhead 12%				83,646
	VAT 5% (UAE)				42,520
	GRAND TOTAL (AED)				893,021

4. EXCLUSIONS

- Mall authorities' fees, NOCs, and Tenant Coordination charges
- IT systems, POS hardware, and security systems (by tenant)
- All signage (internal and external)
- Loose furniture and soft furnishings
- Any structural modifications to slab or columns

5. NOTES

NOTE: This is a SYNTHETIC sample document generated for system testing purposes. All quantities, rates, and figures are illustrative only and do not represent actual market pricing. Replace with real project data before use.